

HS2 Westgate Ventilation Shaft (UK) Shaft Waterproofing

Country

United Kingdom

Type

Railway

Client

High Speed Two (HS2) Limited

Main Contractor

SCS JV (Skanska Costain STRABAG), Joseph Gallagher Ltd.

Execution of the work

Renesco UK Ltd.

Designer

Design House JV (Arup, Typsa, Strabag)

Construction Period

2022-2023

Project Description

High Speed 2 (HS2) is a planned high-speed railway running between London in the South and Manchester and Leeds to the North. Phase1 involves the route between London and Birmingham with approximately 200km of new high-speed rail being laid. The two Main Works Civils lots start from Euston Station in London. S1 includes two 9 km twin bored tunnels between the new HS2 stations, Euston and Old Oak Common. S2 continues from Old Oak Common with 15 km of twin bored tunnels to West Ruislip where there is approximately 5 km of open route before transitioning into C1 lot.


The Westgate Ventilation Shaft in Ealing is one of five shafts along the 8.4-mile Northolt Tunnel route of HS2 including adits, headwalls, and cross-passages, around 35 meters below the surface, wherein the secondary lining is sealed via a sheet membrane system. The shaft will have an internal diameter of 15 m and will be constructed using cavity wall, retaining wall, a poured concrete collar around the shaft, precast rings at the top and using a sprayed concrete lining technique at the bottom. The base slab is 2.3 m thick and constructed in three different pours.


Scope of Service

Supply and Installation of a loose laid waterproofing sheet membrane system under pressurized water conditions, primary lining with fiber-reinforced shotcrete, sheet waterproofing according to BS8102 (British standard), full-round (360°) sealing, secondary lining via cast-in-place concrete and the option for remedial grouting/injection works.

- Sheet membrane. PVC-P. 2 mm
- 1'200 g/sqm PP protection geotextile
- Protection sheet membrane, 1.5 mm
- Water barriers, 400/30/6, PVC-P
- Termination at pre-cast-concrete-elements with adhesive strips/tapes
- Injection system, active control sockets, injection hoses, hydrophilic swelling profiles
- BA-Anchors
- Temporary underslab drainage







- 1. Waterproofing at main shaft/ base slab
- 2. Overview
- 3. Waterproofing works in adits